

DIVISION 22: PLUMBING

22 0000

PLUMBING

22 0501	COMMON PLUMBING REQUIREMENTS
22 0503	PIPE, PIPE FITTINGS, PIPE HANGERS & VALVES
22 0553	IDENTIFICATION FOR PLUMBING PIPES AND EQUIPMENT
22 0703	MECHANICAL INSULATION AND FIRE STOPPING
22 0705	UNDERGROUND PIPING INSULATION
22 0710	POTABLE WATER PIPE INSULATION
22 0711	HANDICAPPED FIXTURES INSULATION
22 0800	FIRE STOPPING

22 1000

PLUMBING PIPING AND VALVES

22 1110	DOMESTIC WATER PIPING, HOT AND COLD POTABLE WATER DISTRIBUTION
22 1123	NATURAL GAS SYSTEMS
22 1313	SOIL, WASTE, & VENT PIPING SYSTEMS

22 3000

PLUMBING EQUIPMENT

22 3330	ELECTRIC STORAGE TYPE WATER HEATERS
---------	-------------------------------------

22 4000

PLUMBING FIXTURES

22 4001	PLUMBING FIXTURES
---------	-------------------

DIVISION 22 PLUMBING

SECTION 22 0501 - COMMON PLUMBING REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and General Provisions of Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Furnish labor, materials, and equipment necessary for completion of work as described in Contract Documents.
- B. It is the intent of these specifications that the systems specified herein are to be complete and operational before being turned over to the owner. During the bidding process, the contractor is to ask questions or call to the engineer's attention any items that are not shown or may be required to make the system complete and operational. Once the project is bid and the contractor has accepted the contract, it is his responsibility to furnish and install all equipment and parts necessary to provide a complete and operational system without additional cost to the owner.
- C. Furnish and install fire stopping materials to seal penetrations through fire rated structures and draft stops.

1.3 SUBMITTALS

- A. Substitutions: By specific designation and description, standards are established for specialties and equipment. Other makes of specialties and equipment of equal quality will be considered provided such proposed substitutions are submitted to the Architect for his approval, complete with specification data showing how it meets the specifications, at least 5 working days prior to bid opening. A list of approved substitutions will be published as an addendum.
 - 1. Submit a single copy of Manufacturer's catalog data including Manufacturer's complete specification for each proposed substitution.
 - 2. The Architect or Engineer is to be the sole judge as to the quality of any material offered as an equal.
- B. Product Data, Shop Drawings: Within 30 days after award of contract, submit 10 sets of Manufacturer's catalog data for each manufactured item.
 - 1. Literature shall include enough information to show complete compliance with Contract Document requirements.
 - 2. Mark literature to indicate specific item with applicable data underlined.
 - 3. Information shall include but not be limited to capacities, ratings, type of material used, guarantee, and such dimensions as are necessary to check space requirements.
 - 4. When accepted, submittal shall be an addition to Contract Documents and shall be in equal force. No variation shall be permitted.
 - 5. Even though the submittals have been accepted by the Engineer, it does not relieve the contractor from meeting all of the requirements of the plans and specifications and providing a complete and operational system.
- C. Drawings of Record: One complete set of blue line mechanical drawings shall be provided for the purpose of showing a complete picture of the work as actually installed.

1. These drawings shall serve as work progress report sheets. Contractor shall make notations neat and legible therein daily as the work proceeds.
2. The drawings shall be kept at the job at a location designated by the Mechanical Engineer.
3. At completion of the project these "as-built" drawings shall be signed by the Contractor, dated, and returned to the Architect.

1.4 QUALITY ASSURANCE

- A. Requirements of Regulatory Agencies:
 1. Perform work in accordance with applicable provisions of local and state Plumbing Code, Gas Ordinances, and adoptions thereof. Provide materials and labor necessary to comply with rules, regulations, and ordinances.
 2. In case of differences between building codes, state laws, local ordinances, utility company regulations, and Contract Documents, the most stringent shall govern. Promptly notify Architect in writing of such differences.
- B. Applicable Specifications: Referenced specifications, standards, and publications shall be of the issues in effect on date of Advertisement for Bid.
 1. "Heating, Ventilating and Air Conditioning Guide" published by the American Society of Heating and Air Conditioning Engineers.
 2. "Engineering Standards" published by the Heating, Piping, and Air Conditioning Contractors National Association.
 1. "2012 International Building Code", "2012 International Mechanical Code", and "2012 International Fire Code" as published by the International Conference of Building Officials.
 2. 2012 Idaho Plumbing Code as published by the International Association of Plumbing and Mechanical Officials.
 3. "National Electrical Code" as published by the National Fire Protection Association.
 4. "2012 International Energy Conservation Code".

1.5 INSPECTIONS AND PERMITS

- A. Pay for permits, fees, or charges for inspection or other services. Local and state codes and ordinances must be properly executed without expense to Owner and are considered as minimum requirements. Local and state codes and ordinances do not relieve the Contractor from work shown that exceeds minimum requirements.

1.6 ADDITIONAL WORK:

- A. Design is based on equipment as described in the drawing equipment schedule. Any change in foundation bases, electrical wiring, conduit connections, piping, controls and openings required by alternate equipment submitted and approved shall be paid for by this division. All work shall be in accordance with the requirements of the applicable sections.

PART 2 - NOT USED

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Site Inspection:
 1. Examine premises and understand the conditions which may affect performance of work of this Division before submitting proposals for this work.

2. No subsequent allowance for time or money will be considered for any consequence related to failure to examine site conditions.

B. Drawings:

1. Mechanical drawings show general arrangement of piping, ductwork, equipment, etc, and do not attempt to show complete details of building construction which affect installation. This Contractor shall refer to architectural, structural, and electrical drawings for additional building detail which affect installation of his work.
 - a. Follow mechanical drawings as closely as actual building construction and work of other trades will permit.
 - b. No extra payments will be allowed where piping and/or ductwork must be offset to avoid other work or where minor changes are necessary to facilitate installation.
 - c. Everything shown on the mechanical drawings shall be the responsibility of Mechanical Contractor unless specifically noted otherwise.
2. Consider architectural and structural drawings part of this work insofar as these drawings furnish information relating to design and construction of building. These drawings take precedence over mechanical drawings.
3. Because of small scale of mechanical drawings, it is not possible to indicate all offsets, fittings, and accessories which may be required. Investigate structural and finish conditions affecting this work and arrange work accordingly, providing such fittings, valves, and accessories required to meet conditions. Do not scale drawings for locations of equipment or piping. Refer to large scale dimensioned drawings for exact locations.

C. Insure that items to be furnished fit space available. Make necessary field measurements to ascertain space requirements including those for connections and furnish and install equipment of size and shape so final installation shall suit true intent and meaning of Contract Documents.

1. If approval is received to use other than specified items, responsibility for specified capacities and insuring that items to be furnished will fit space available lies with this Division.
2. If non-specified equipment is used and it will not fit job site conditions, this Contractor assumes responsibility for replacement with items named in Contract Documents.

3.2 PREPARATION

- A. Cut carefully to minimize necessity for repairs to existing work. Do not cut beams, columns, or trusses.
1. Patch and repair walls, floors, ceilings, and roofs with materials of same quality and appearance as adjacent surfaces unless otherwise shown. Surface finishes shall exactly match existing finishes of same materials.
 2. Each Section of this Division shall bear expense of cutting, patching, repairing, and replacing of work of other Sections required because of its fault, error, tardiness, or because of damage done by it.
 3. Cutting, patching, repairing, and replacing pavements, sidewalks, roads, and curbs to permit installation of work of this Division is responsibility of Section installing work.

3.3 INSTALLATION

- A. Arrange pipes, ducts, and equipment to permit ready access to valves, unions, traps, starters, motors, control components, and to clear openings of doors and access panels.

3.4 STORAGE AND PROTECTION OF MATERIALS:

- A. Provide storage space for storage of materials and assume complete responsibility for losses due to any cause whatsoever. Storage shall not interfere with traffic conditions in any public thoroughfare.

- B. Protect completed work, work underway, and materials against loss or damage.
- C. Close pipe openings with caps or plugs during installation. Cover fixtures and equipment and protect against dirt, or injury caused by water, chemical, or mechanical accident.

3.5 EXCAVATION AND BACKFILL

- A. Perform necessary excavation of whatever substance encountered for proper laying of all pipes and underground ducts.
 - 1. Excavated materials not required for fill shall be removed from site as directed by Engineer.
 - 2. Excavation shall be carried low enough to allow a minimum coverage over underground piping of 5'-0" or to be below local frost level.
 - 3. Excess excavation below required level shall be backfilled at Contractor's expense with earth, sand, or gravel as directed by Engineer. Tamp ground thoroughly.
 - 4. Ground adjacent to all excavations shall be graded to prevent water running into excavated areas.
- B. Backfill pipe trenches and allow for settlement.
 - 1. Backfill shall be mechanically compacted to same density as surrounding undisturbed earth.
 - 2. Cinders shall not be used in backfilling where steel or iron pipe is used.
 - 3. No backfilling shall be done until installation has been approved by the Engineer.

3.6 COOPERATION

- A. Cooperate with other crafts in coordination of work. Promptly respond when notified that construction is ready for installation of work under Division 22. Contractor will be held responsible for any delays which might be caused by his negligence or failure to cooperate with the other Contractors or crafts.

3.7 SUPERVISION

- A. Provide a competent superintendent in charge of the work at all times. Anyone found incompetent shall be removed at once and replaced by someone satisfactory, when requested by the Architect.

3.8 INSTALLATION CHECK:

- A. An experienced, competent, and authorized representative of the manufacturer or supplier of each item of equipment indicated in the equipment schedule shall visit the project to inspect, check, adjust if necessary, and approve the equipment installation. In each case, the equipment supplier's representative shall be present when the equipment is placed in operation. The equipment supplier's representative shall revisit the project as often as necessary until all trouble is corrected and the equipment installation and operation is satisfactory to the Engineer.
- B. Each equipment supplier's representative shall furnish to the Owner, through the Engineer, a written report certifying the following:
 - 1. Equipment has been properly installed and lubricated.
 - 2. Equipment is in accurate alignment.
 - 3. Equipment is free from any undue stress imposed by connecting piping or anchor bolts.
 - 4. Equipment has been operated under full load conditions.
 - 5. Equipment operated satisfactorily.
- C. All costs for this installation check shall be included in the prices quoted by equipment suppliers.

3.9 CLEANING EQUIPMENT AND PREMISES

- A. Properly lubricate equipment before Owner's acceptance.
- B. Clean exposed piping, equipment, and fixtures. Repair damaged finishes and leave everything in working order.
- C. Remove stickers from fixtures and adjust flush valves.
- D. Trap elements shall be removed during cleaning and flushing period. Replace trap elements and adjust after cleaning and flushing period.

3.10 TESTS

- A. No piping work, fixtures, or equipment shall be concealed or covered until they have been inspected and approved by the inspector. Notify inspector when the work is ready for inspection.
- B. All work shall be completely installed, tested as required by Contract Documents and the city and county ordinances and shall be leak-tight before the inspection is requested.
- C. Tests shall be repeated to the satisfaction of those making the inspections.
- D. Water piping shall be flushed out, tested at 100 psi and left under pressure of supply main or a minimum of 40 psi for the balance of the construction period.

3.11 WARRANTY

- A. Contractor shall guarantee work under Division 22 to be free from inherent defects for a period of one year from acceptance.
 - 1. Contractor shall repair, revise or replace any and all such leaks, failure or inoperativeness due to defective work, materials, or parts free of charge for a period of one year from final acceptance, provided such defect is not due to carelessness in operation or maintenance.
- B. In addition to warranty specified in General Conditions and plumbing systems are to be free from noise in operation that may develop from failure to construct system in accordance with Contract Documents.

3.12 SYSTEM START-UP, OWNER'S INSTRUCTIONS

- A. Owner's Instructions
 - 1. Instruct building maintenance personnel and Owner Representative in operation and maintenance of mechanical systems utilizing Operation & Maintenance Manual when so doing.
 - 2. Minimum instruction periods shall be as follows –
 - a. Plumbing - Four hours.
 - 3. Instruction periods shall occur after Substantial Completion inspection when systems are properly working and before final payment is made.
 - 4. None of these instructional periods shall overlap another.

END OF SECTION 22 0501

SECTION 22 0503 - PIPE, PIPE FITTINGS, PIPE HANGERS & VALVES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 22 05 01 apply to this Section.

1.2 SUMMARY

- A. General piping and valve materials and installation procedures for all piping systems.

1.3 QUALITY ASSURANCE

- A. Manufacture:
 - 1. Use domestic made valves, pipe and pipe fittings.
- B. General: Support components shall conform to Manufacturer's Standardization Society Specification SP-58.

PART 2 - PRODUCTS

2.1 VALVES

- A. Ball Valves:
 - 1. 2" and smaller for domestic water service:
 - a. Milwaukee BA-100, bronze, screwed, 600# WOG ball valve with Teflon seats
 - b. Victaulic S/722.
 - 2. 2" and smaller for heating hot water service:
 - a. Milwaukee BA-100, bronze, screwed, 600# WOG ball valve with Teflon seats
 - b. Victaulic S/722.
 - 3. 2½" and larger - 3 piece full port, bronze, flanged 400# WOG with seats rated for temperature service.
 - 4. Ball valves shall be used where ever possible.
- B. Cutoff service valves may be gate Valves:
 - 1. Up to 2" inclusive: Milwaukee No. 148
 - 2. 2 1/2" and larger: Milwaukee No. F-2885
- C. Check Valves:
 - 1. Up to 2" inclusive: Milwaukee No. 509
 - 2. 2 1/2" and larger:
 - a. Milwaukee No. F-2974
 - b. Victaulic 716, 779
- D. Stop and Waste Cocks:
 - 1. Milwaukee No. F-2885 with 3/4" Milwaukee No. 105 gate valve tapped into pipe on outlet side of main valve.
- E. Use ball valves or butterfly valves everywhere unless noted otherwise.
- F. Approved Manufacturers:
 - 1. Crane

2. Nibco
3. Hammond
4. Stockham
5. Milwaukee
6. Victaulic

2.2 PIPE

- A. Exposed waste, vent and water piping connections to fixtures shall be chrome plated.
- B. Roof Drain Piping: Above grade - up to 3" - Schedule 40-A-120 galvanized steel pipe with galvanized banded fittings or cast iron soil pipe with no-hub fittings. Below grade and over 3" shall be service weight cast iron soil pipe and fittings.
- C. Sewer Piping: Beyond 5'-0" from the building lines - SDR-35 PVC sewer pipe or concrete sewer pipe as approved by local code. Bed piping in sandfill.
- D. Condensate Drain Piping: Type "M" copper with sweat fittings or Schedule 40 PVC pipe and fittings.

2.3 PIPE HANGERS

- A. Adjustable, malleable iron clevis type of a diameter adequate to support pipe size.
- B. Approved Manufacturers:
 1. B-Line Systems Fig. B3100
 2. Grinnell No. 260
 3. Kin-Line 455
 4. Superstrut CL-710

2.4 INSULATING COUPLINGS

- A. Suitable for at least 175 PSIG WP at 250 deg F.
- B. Approved Manufacturers:
 1. Central Plastics Co
 2. Victaulic Co
 3. Watts Regulator Co

2.5 EXPANSION JOINTS

- A. Install at all building expansion joints and as shown on the drawings, flexible, or nipple/flexible coupling combinations for added expansion/deflection. Submit Manufacturer's data.
- B. Approved Manufacturers
 1. Victaulic Style 155, 150
 2. Grinnell - Gruv-Lok
 3. Garlock Garlflex 8100
 4. Vibration Mountings & Controls, Inc.

2.6 SLEEVES

- A. Sleeves shall be standard weight galvanized iron pipe, Schedule 40 PVC, or 14 gauge galvanized sheet metal two sizes larger than pipe or insulation.

- B. Steel or heavy steel metal of the telescoping type of a size to accommodate pipe and covering wherever it passes through floors, walls, or ceilings.

2.7 INTERMEDIATE ATTACHMENTS

- A. Continuous threaded rod may be used wherever possible.
- B. No chain, wire, or perforated strap shall be used.

2.8 FLOOR AND CEILING PLATES

- A. Brass chrome plated

2.9 APPROVED MANUFACTURERS - Grinnell and Fee/Mason

- A. Concrete Inserts: Grinnell Fig. 282
- B. Pipe Hanger Flange: Grinnell Fig. 163
- C. Vertical Pipe: Grinnell Fig. 261 or equal.
- D. Cast Iron Pipe: Grinnell Fig. 260 clevis hanger or equal
- E. Pipe Attachments for steel pipe with 1" or less of insulation:
 - 1. Grinnell Fig. 108 ring
 - 2. Grinnell Fig. 114 turnbuckle adjuster
 - 3. Or equal

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Furnish and install complete system of piping, valved as indicated or as necessary to completely control entire apparatus. Pipe drawings are diagrammatic and indicate general location and connections. Piping may have to be offset, lowered, or raised as required or directed at site. This does not relieve this Contractor from responsibility for proper erection of systems of piping in every respect.
- B. Properly support piping and make adequate provisions for expansion, contraction, slope, and anchorage.
 - 1. Cut piping accurately for fabrication to measurements established at site and work into place without springing or forcing.
 - 2. Do not use pipe hooks, chains, or perforated metal for pipe support.
 - 3. Remove burr and cutting slag from pipes.
 - 4. Make changes in direction with proper fittings.
 - 5. Insulate hangers for copper pipe from piping by means of at least two layers of Scotch 33 plastic tape.
 - 6. Support piping at 8 feet on center maximum for pipe 1-1/4 inches or larger and 6 feet on center maximum for pipe one inch or less. Provide support at each elbow. Install additional support as required.
 - 7. Suspend piping from roof trusses or clamp to vertical walls using Unistrut and clamps (except underground pipe). Laying of piping on any building member is not allowed.
- C. Arrange piping to not interfere with removal of other equipment, ducts, or devices, or block access to doors, windows, or access openings. Provide accessible, ground joint unions in piping at connections to equipment.
- D. Make connections of dissimilar metals with insulating couplings.

- E. Provide sleeves around pipes passing through floors, walls, partitions, or structural members.
 - 1. Seal sleeves with plastic or other acceptable material.
 - 2. Do not place sleeves around soil, waste, vent, or roof drain lines passing through concrete floors on grade.
- F. Cap or plug open ends of pipes and equipment to keep dirt and other foreign materials out of system. Do not use plugs of rags, wool, cotton waste, or similar materials.
- G. Install piping systems so they may be easily drained.
- H. Grade soil and waste lines within building perimeter 1/4 inch fall per ft in direction of flow.
- I. Insulate water piping buried within building perimeter.
 - 1. Do not use reducing bushings, street elbows, or close nipples.
 - 2. Bury water piping 6 inches minimum below bottom of slab and encase in 2 inches minimum of sand.
 - 3. Do not install piping in shear walls.

3.2 HORIZONTAL PIPING INSTALLATION

- A. Locate hangers, supports, and anchors near or at changes in piping direction and concentrated loads.
- B. Provide for vertical adjustment to maintain pitch required for proper drainage.
- C. Allow for expansion and contraction of the piping.

3.3 PIPE SLEEVES AND INSERTS

- A. Set sleeves before concrete is poured or floors finished.
- B. Inserts for units should be placed in the concrete or masonry during construction to avoid cutting of finished work. When and if cutting becomes necessary, it must be done in accordance with the cutting and patching specifications.

3.4 FLOOR AND CEILING PLATES

- A. Install on all pipes passing through floors, partitions, and ceilings.

3.5 UNIONS AND CONNECTIONS

- A. Install malleable ground joint unions in hot and cold water piping throughout the system so that any portion can be taken down for repairs or inspections without injury to same or covering.
- B. Running threads or long screws will not be permitted in jointing any pipe.
- C. Provide dielectric waterways Style #47 between ferrous and non-ferrous metals.

3.6 FIRE STOPPING

- A. Fire stop all penetrations of fire walls, fire barriers, fire partitions, and other fire rated walls and ceilings and floors as per IBC Section 711. See Specification 22 0800.

END OF SECTION 22 0503

SECTION 22 0553 - IDENTIFICATION FOR PLUMBING PIPES AND EQUIPMENT

PART 1 - GENERAL

1.1 SUMMARY

- A. Includes But Not Limited To:
 - 1. Furnish and install identification of plumbing piping and equipment as described in Contract Documents.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Paint:
 - 1. One Coat Primer:
 - a. 6-2 Quick Drying Latex Primer Sealer over fabric covers.
 - b. 6-205 Metal Primer under dark color paint.
 - c. 6-6 Metal Primer under light color paint.
 - 2. Finish Coats: Two coats 53 Line Acrylic Enamel.
 - 3. Performance Standard: Paints specified are from Pittsburgh Paint & Glass (PPG), Pittsburgh, PA www.pittsburghpaints.com or PPG Canada Inc, Mississauga, ON (800) 263-4350 or (905) 238-6441
 - 4. Type Two Acceptable Products. See Section 01 6200.
 - a. Paint of equal quality from following Manufacturers may be submitted for Architect's approval before use. Maintain specified colors, shades, and contrasts.
 - 1) Benjamin Moore, Montvale, NJ www.benjaminmoore.com or Toronto, ON (800) 304-0304 or (416) 766-1176.
 - 2) ICI Dulux, Cleveland, OH or ICI Paints Canada Inc, Concord, ON www.dulux.com.
 - 3) Sherwin Williams, Cleveland, OH www.sherwin-williams.com.

2.2 VALVE IDENTIFICATION

- A. Make a list of and tag all valves installed in this work.
 - 1. Valve tags shall be of brass, not less than 1"x2" size, hung with brass chains.
 - 2. Tag shall indicate plumbing or heating service.

PART 3 - EXECUTION

3.1 SCHEDULES

- A. Pipe Identification Schedule:
 - 1. Apply stenciled symbols as follows:

Pipe Use	Abbreviation
Domestic Cold Water	CW
Domestic Hot Water	HW

END OF SECTION 22 0553

SECTION 22 0703 - MECHANICAL INSULATION AND FIRE STOPPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 22 05 01 apply to this Section.

1.2 SUMMARY

- A. Furnish and install mechanical insulation and fire stopping as described in Contract Documents including but not limited to the following:
 - 1. Cold Water and Rain Drain Piping Insulation
 - 2. Hot Water Piping Insulation (Domestic)
 - 3. Fire Stopping

1.3 QUALITY ASSURANCE

- A. Insulation shall have composite (insulation, jacket or facing and adhesive used to adhere facing or jacket to insulation) fire and smoke hazard ratings as tested by Procedure ASTM E-84, NFPA 255 and UL 723 not exceeding: Flame Spread of 25 and Smoke Developed of 50.
- B. Insulation Contractor shall certify in writing, prior to installation, that all products to be used will meet the above criteria.
- C. Accessories, such as adhesives, mastics, cements, and tapes, for fittings shall have the same component ratings as listed above.
- D. Products, or their shipping cartons, shall bear a label indicating that flame and smoke ratings do not exceed above requirements.
- E. Any treatment of jacket or facings to impart flame and smoke safety shall be permanent.
- F. The use of water-soluble treatments is prohibited.

END OF SECTION 22 0703

SECTION 22 0705 - UNDERGROUND PIPING INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 22 05 01 apply to this Section.

1.2 SUMMARY

- A. Furnish and install insulation on underground hot and cold water pipes within confines of building as described in Contract Documents.

PART 2 - PRODUCTS

2.1 MATERIAL

- A. Insulation:
 - 1. 1/2 inch thick Armaflex Standard Pipe Insulation
 - 2. Equal by Rubatex
 - 3. Equal by Imcolock
- B. Joint Sealant:
 - 1. Armstrong 520

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Slip underground pipe insulation onto pipe and seal butt joints.
- B. Where slip-on technique is not possible, slit insulation, apply to pipe, and seal seams and joints.

END OF SECTION 22 0705

SECTION 22 0710 - POTABLE WATER PIPE INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 22 05 01 apply to this Section.

1.2 SUMMARY

- A. Furnish and install insulation on above ground hot and cold water lines, fittings, valves, pump bodies, flanges, and accessories as described in Contract Documents.

PART 2 - PRODUCTS

2.1 INSULATION

- A. One inch thick snap-on glass fiber pipe insulation.
- B. Heavy density pipe insulation with factory vapor jacket equal to Fiberglass ASJ may be used.
- C. Approved Manufacturers:
 - 1. CTM
 - 2. Manville
 - 3. Owens-Corning
 - 4. Knauf

2.2 PVC FITTING, VALVE, & ACCESSORY COVERS

- A. Approved Manufacturers:
 - 1. Knauf
 - 2. Zeston

PART 3 - EXECUTION

3.1 APPLICATION

- A. Piping:
 - 1. Apply insulation to clean, dry piping with joints tightly butted.
 - 2. Adhere "factory applied vapor barrier jacket lap" smoothly and securely at longitudinal laps with a white vapor barrier adhesive.
 - 3. Adhere 3 inch wide self-sealing butt joint strips over end joints.
- B. Fittings, Valves, & Accessories:
 - 1. Insulate with same type and thickness of insulation as pipe, with ends of insulation tucked snugly into throat of fitting and edges adjacent to pipe insulation tufted and tucked in.
 - 2. Cover insulation with one piece fitting cover secured by stapling or taping ends to adjacent pipe covering.
- C. Pipe Hangers:
 - 1. Do not allow pipes to come in contact with hangers.
 - 2. Provide 16 ga x 6 inch long galvanized shields at each pipe hanger to protect pipe insulation from crushing by clevis hanger.

END OF SECTION 22 0710

SECTION 22 0711 - HANDICAPPED FIXTURES INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 22 05 01 apply to this Section.

1.2 SUMMARY

- A. Furnish and install handicapped fixtures insulation as described in Contract Documents.

1.3 QUALITY ASSURANCE

- A. Insulating device must comply with UBC-85 and federal accessibility standards.
- B. Cover must meet federal standards for protection from burns and abrasions.

PART 2 - PRODUCTS

2.1 MANUFACTURED UNITS

- A. Insulating device shall be molded fire resistant foam, to encapsulate hot water piping, stop, and P-trap.
 - 1. Approved Manufacturers:
 - a. TCI Products' Skal+Gard SG-100B
- B. Safety cover with recloseable sealing strips which allow for removal and replacement for line maintenance may be used on drain and supply lines under lavatories.
 - 1. Approved Manufacturers:
 - a. Handy-Shield
 - b. Plumberex
- C. Color shall be white.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install tamper-proof locking strap to discourage pilferage.

END OF SECTION 22 0711

SECTION 22 0800 - FIRE STOPPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 22 05 01 apply to this Section.

1.2 SUMMARY

- A. Furnish and install fire stopping as described in Contract Documents.

1.3 QUALITY ASSURANCE

- A. Fire stopping material shall meet ASTM E814, E84 and be UL listed.

PART 2 - PRODUCTS

2.1 MANUFACTURED UNITS

- A. Material shall be flexible, long lasting, intumescent acrylic seal to accommodate vibration and building movement.
- B. Caulk simple penetrations with gaps of 1/4" or less with:
 - 1. Dow Corning Fire Stop Sealant
 - 2. Pensil 300
- C. Caulk multiple penetrations and/or penetrations with gaps in excess of 1/4" with:
 - 1. Dow Corning Fire Stop Foam
 - 2. Pensil 200
 - 3. IPC flame safe FS-1900
 - 4. Tremco "Tremstop 1A"

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Follow manufacturer's installation instructions explicitly.
- B. Seal penetrations of ductwork, piping, and other mechanical equipment through one-hour and two-hour rated partitions as shown on Architectural and Mechanical Drawings.
- C. Install fire stopping material on clean surfaces to assure adherence.

END OF SECTION 22 0800

SECTION 22 1110 - DOMESTIC WATER PIPING, HOT AND COLD POTABLE WATER DISTRIBUTION

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes ASTM F877 cross-linked polyethylene (PEX) tubing hot and cold water distribution systems, ASTM F876 cross-linked polyethylene (PEX) tube, ASTM F1807 fittings and ASTM F2159 fittings

1.2 REFERENCES

- A. ASTM International
 - 1. ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials.
 - 2. ASTM F876 Standard Specification for Cross-linked Polyethylene (PEX) Tubing.
 - 3. ASTM F877 Standard Specification for Cross-linked Polyethylene (PEX) Plastic Hot and Cold Water Distribution Systems
 - 4. ASTM F1807 Standard Specification for Metal Insert Fittings Utilizing a Copper Crimp Ring for SDR9 Cross-linked Polyethylene (PEX) Tubing
 - 5. ASTM F2159 Standard Specification for Plastic Insert Fittings Utilizing a Copper Crimp Ring for SDR9 Cross-linked Polyethylene (PEX) Tubing
- B. National Sanitation Foundation (NSF)
 - 1. Standard 14 Plastics Piping System Components and Related Materials
 - 2. Standard 61 Drinking Water System Components – Health Effects
- C. International Code Council (ICC)
 - 1. International Mechanical Code
 - 2. International Plumbing Code
- D. International Association of Plumbing Officials (IAPMO)
 - 1. Uniform Plumbing Code
 - 2. Uniform Mechanical Code
- E. Plastic Pipe Institute (PPI)
 - 1. Technical Report TR-3 Policies and Procedures for Developing Recommended Hydrostatic Design Stresses for Thermoplastic Pipe Materials.
 - 2. Technical Report TR-4 Recommended Hydrostatic Strengths and Design Stresses for Thermoplastic Piping and Fitting Compounds

1.3 SYSTEM DESCRIPTION

- A. A. Design Requirements
 - 1. Standard Grade hydrostatic pressure ratings from the Plastic Pipe Institute in accordance with TR-3 and listed in TR-4. The following three standard-grade hydrostatic ratings are required;
 - a. 200 degrees F at 80 psi
 - b. 180 degrees F at 100 psi
 - c. 73 degrees F at 160 psi
 - 2. Tubing tested in general accordance with ASTM E84 for a flame spread/smoke developed index of 25/50 or less for the following PEX tube sizes encased with ½ inch fiberglass insulation;
 - a. 1 ¼ inch

- b. 1 ½ inch
 - c. 2 inch
 - 3. Tubing tested in general accordance with ASTM E84 for a flame spread/smoke developed index of 25/50 or less for the following PEX tube sizes;
 - a. 3/8 inch
 - b. ½ inch
 - c. 5/8 inch
 - d. ¾ inch
 - e. 1 inch
- B. Performance Requirements
 - 1. To provide a PEX tubing hot and cold potable water distribution system, which is manufactured, fabricated and installed to comply with regulatory agencies and to maintain performance criteria stated by the PEX tubing manufacturer without defects, damage or failure
 - a. Comply with NSF Standard 14
 - b. Comply with NSF Standard 61
 - c. Show compliance with ASTM F877

1.4 SUBMITTALS

- A. General
 - 1. Upon request, submit listed submittals in accordance with Conditions of the Contract and Division 1 Submittal Procedures Section
- B. Product Data
 - 1. Upon request, submit manufacturer's product submittal data and installation instructions
 - 2. Upon request, submit manufacturer's Professional Installation Limited Warranty
- C. Shop Drawings
 - 1. Upon request, provide installation drawings indicating tubing layout, manifold locations, plumbing fixtures supported and schedules with details required for installation of the system
- D. Samples
 - 1. Upon request, submit selection and verification samples of piping
- E. Listing Certifications
 - 1. Upon request, submit manufacturers third party listings

1.5 QUALITY ASSURANCE

- A. Installer Qualifications
 - 1. Utilize an installer having demonstrated experience on projects of similar size and complexity and possesses the skills and knowledge to install a PEX potable water distribution system
 - 2. Installer will utilize skilled workers holding a trade qualification license or equivalent or apprentices under the supervision of a licensed tradesperson
- B. Pre-installation Meetings
 - 1. Verify project timeline requirements
 - 2. Manufacturer's installation instruction
 - 3. Manufacturer's warranty requirements

1.6 DELIVERY, STORAGE AND HANDLING

- A. General
 - 1. Comply with Division 1 Product Requirement Section
- B. Delivery
 - 1. Deliver materials in manufacture's original, unopened, undamaged containers with identification labels intact until ready for installation
- C. Storage and Protection
 - 1. Store materials protected from exposure to harmful environmental conditions and at temperature and humidity conditions recommended by the manufacturer
 - 2. Store PEX tubing indoors, in cartons or under cover to avoid dirt or foreign material from entering the tubing
 - 3. Do not expose PEX tubing to direct sunlight for more than six months. If construction delays are encountered, cover the tubing that is exposed to direct sunlight

1.7 WARRANTY

- A. Project Warranty
 - 1. Refer to Conditions of the Contract for project warranty provisions
- B. Manufacturer's Warranty
 - 1. Shall cover the repair or replacement of properly installed tubing and fittings proven defective as well as incidental damages
 - 2. Warranty period for PEX tubing and subsequent system shall be 25 year non-prorated warranty against failure due to defect in material or workmanship, beginning with the date of installation
 - 3. It is the installer's responsibility to avoid mixing fittings manufactured by others as it will reduce the owner's warranty

PART 2 - PRODUCTS

2.1 PRODUCT MANUFACTURERS

- A. Zurn
- B. Uponor
- C. Vanguard
- D. Rehau
- E. Viega

2.2 MATERIALS

- A. Tubing
 - 1. Cross-linked polyethylene (PEX).
 - 2. Non-barrier type.
 - a. Shall have a pressure and temperature rating of 160 PSI at 73°F, 100 PSI at 180°F and 80 PSI at 200°F.
 - b. Tubing shall have a minimum of 6 months UV protection.
 - 3. Manufactured in accordance with ASTM F876 and ASTM F877 and tested for compliance by an independent third-party agency.
- B. Fittings

1. Manufactured in accordance with ASTM F1807 or ASTM F2159 and/or comply with ASTM F877 system standard as identified on the fitting
- C. Manifold
 1. Preassembled Manifold
 2. Copper Manifold System
 3. Multi Port Fittings
 4. Copper Manifold Header
- D. Valves
 1. Shall be of the metal type, meeting the requirements of ASTM F877, identified as such with the appropriate mark on the product

PART 3 - EXECUTION

3.1 MANUFACTURER'S INSTRUCTIONS

- A. A. Comply with manufacture's product data, including product technical bulletins, technical memo's, installation instructions and design drawings.

3.2 EXAMINATION

- A. Site Verification of Conditions
 1. Verify that site conditions are acceptable for the installation of the PEX potable water system
 2. Do not proceed with installations of the PEX potable water system until unacceptable conditions are corrected

3.3 INSTALLATION

- A. Install PEX tubing in accordance with tubing manufacturer's recommendations and as indicated in the PEX Plumbing Installation Guide
- B. Do not install PEX tubing within 6 inches of gas appliance vents or within 12 inches of any recessed light fixtures
- C. Do not solder within 18 inches of PEX tubing in the same waterline. Make sweat connections prior to making PEX connections
- D. Ensure no glues, solvents, sealants or chemicals come in contact with the tubing without prior permission from the tubing manufacturer
- E. Do not expose PEX tubing to direct sunlight for more than 6 months
- F. Use grommets or sleeves at the penetration for PEX tubing passing through metal studs
- G. Use a PEX manufacturer recommended fire stop sealant manufacturer
- H. Protect PEX tubing with sleeves where abrasion may occur
- I. Use nail plates where PEX tubing penetrates wall stud or joists and has the potential for being struck with a screw or nail
- J. Allow slack of approximately 1/8 inch per foot of tube length to compensate for expansion and contraction

- K. Minimum horizontal supports are to be installed not less than 32 inches between hangers in accordance with model plumbing codes.
- L. Pressurize PEX tubing in accordance with applicable codes or in the absence of applicable codes, test pressure shall be at least equal to normal system working pressure, but not less than 40 PSI water or air and not greater than 225 PSI water, 125 PSI air

3.4 FIELD QUALITY CONTROL

- A. Site Tests
 - 1. To ensure system integrity, pressure test the system before covering tubing in concrete and after other trades have worked in the vicinity of the tubing
 - 2. Repair and replace any product that has been damaged according to manufacturer's recommendation

3.5 PROTECTION

- A. Protect installed work from damage due to subsequent construction activity on the site

END OF SECTION 22 1110

SECTION 23 1123 – NATURAL GAS SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 05 01 apply to this Section.

1.2 SUMMARY

- A. Furnish and install gas piping and fittings within building including connection to meter.

1.3 QUALITY ASSURANCE

- A. Qualifications:
 - 1. Welders shall be certified and bear evidence of certification 30 days prior to commencing work on project. If there is doubt as to proficiency of welder, Owner's Representative may require welder to take another test. This shall be done at no cost to Owner. Certification shall be by Pittsburgh Testing Laboratories or other approved authority.

PART 2 - PRODUCTS

2.1 PIPE

- A. Meet requirements of ASTM A 53-89a, "Specification for Pipe, Steel, Black & Hot-Dipped Zinc-Coated Welded & Seamless".
- B. Carbon steel, butt welded, Schedule 40 black steel pipe.

2.2 FITTINGS

- A. Black Pipe:
 - 1. Welded forged steel fittings meeting requirements of ASTM A 234-89a, "Specification for Piping Fittings of Wrought Carbon Steel and Alloy Steel for Moderate and Elevated Temperatures", or standard weight malleable iron screwed.

2.3 VALVES

- A. 125 psi bronze body ball valve, UL listed
- B. Approved Manufacturers & Models:
 - 1. ConBraCo - "Apollo" series 80-100
 - 2. Jenkins - FIG-30-A
 - 3. Jomar - Model T-204
 - 4. McDonald - 3410
 - 5. PGL Corp - "Red Cap" gas ball valve
 - 6. Watts - Model B-6000-UL

2.4 PRESSURE REDUCING REGULATORS

- A. Corrosion Resistant Brass Body.
- B. 1/2" to 4" Threaded NPT

- C. 2" and Above Flanged.
- D. Max Inlet Pressure 10 psi.
- E. Max Outlet Pressure 0.5 psi.
- F. Temperature Capabilities - ~20 to 180° F.
- G. Approved Manufactures and Models.
 - 1. Emerson Process Management.
 - 2. Maxitrol 3UP33
 - 3. Or approved equal.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Pipe installed underground, through air plenums, in walls, and pipes 2-1/2 inches and larger shall have welded fittings and joints. Other pipe may have screwed or welded fittings.
- B. Wrap and lay underground pipe in accordance with local gas utility company regulations and specifications.
- C. Install gas cocks on lines serving boilers, furnaces, duct heaters, and water heaters adjacent to boiler, furnace, or heater on outside of boiler, furnace, or heater cabinet and easily accessible.
- D. Do not use flexible pipe connections to boilers, furnaces, duct heaters, or hot water heaters.
- E. Install dirt leg with pipe cap, 6 inches long minimum, on each vertical gas drop to heating equipment.
- F. Use fittings for changes of direction in pipe and for branch runouts.
- G. Paint exterior exposed gas piping with grey paint to match gas meter.

END OF SECTION 22 1123

SECTION 22 1313 – SOIL, WASTE, & VENT PIPING SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 22 05 01 apply to this Section.

1.2 SUMMARY

- A. Furnish and install soil, waste, and vent piping systems within building and connect with outside utility lines 5 feet out from building where applicable.
- B. Perform excavation and backfill required by work of this Section.

PART 2 - PRODUCTS

2.1 BURIED LINES

- A. ABS-DWV or PVC-DWV plastic waste pipe and fittings as permitted by state and local plumbing code.
- B. Joint Material:
 - 1. ABS-DWV solvent weld fittings

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Do not caulk threaded work.
- B. Slope horizontal pipe at 1/4 in/ft.
- C. Cleanouts:
 - 1. Provide and set full size cleanouts at foot of each riser, and ends of branches from toilets, at points where a change of direction occurs, on exposed and accessible traps, at points where required to remove rust accumulation or other obstructions and as shown on plans. Set screw cap in cleanout with graphite paste. Cleanouts in walls shall be flush and covered with a chrome plated cleanout cover screwed into the cleanout plug. Cleanouts in floors shall be flush using Zurn, Josam, or Wade floor level cleanout fittings. Location of all cleanouts subject to approval of inspector.
- D. Each fixture and appliance discharging water into sanitary sewer or building sewer lines shall have seal trap in connection with complete venting system so gasses pass freely to atmosphere with no pressure or syphon condition on water seal.
- E. Vent entire waste system to atmosphere. Discharge 14 inches above roof. Join lines together in fewest practicable number before projecting above roof. Set back vent lines so they will not pierce roof near edge or valley.
- F. Use torque wrench to obtain proper tension in cinch bands when using hubless cast iron pipe. Butt ends of pipe against centering flange of coupling.

- G. Flash pipes passing through roof with 16 oz sheet copper flashing fitted snugly around pipes and caulk between flashing and pipe with flexible waterproof compound. Flashing base shall be at least 24 inches square.
 - 1. Flashing may be 4 lb per sq ft lead flashing fitted around pipes and turned down into pipe 1/2 inch with turned edge hammered against pipe wall.

3.2 FIELD QUALITY CONTROL

- A. Before piping is covered, conduct tests for leaks and defective work. Notify Architect prior to testing. Correct leaks and defective work. Fill waste and vent system to roof level with water, 10 feet minimum, and show no leaks for two hours.

END OF SECTION 22 1313

SECTION 22 3330 – ELECTRIC STORAGE TYPE WATER HEATERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, and Section 22 05 00 apply to this Section.

1.2 SUMMARY

- A. Furnish and install water heater as specified in Contract Documents.

1.3 SUBMITTALS

- A. Warranty:
 - 1. Submit copy of specified warranty.

1.4 WARRANTY

- A. Three year non-prorated warranty on water heaters of 20 gallon capacity and larger.

PART 2 - PRODUCTS

2.1 MANUFACTURED UNITS

- A. Glass lined storage tank pressure tested and rated for 125 PSI working pressure.
- B. 40 Gallon - (Regular Height)
 - 1. (2) 4.5 Kw non-simultaneous operation.
 - 2. 3 inches minimum glass fiber insulation.
 - 3. Complete with two stage thermostat, magnesium anode, electric sheath rod type heating element, high limit control, and ASME rated temperature-pressure relief valve.
 - 4. Heater shall be pre-wired and entire unit bear UL label.
 - 5. Maximum Height - 50 inches.
 - 6. Approved Manufacturers:
 - a. A O Smith
 - b. State Industries
 - c. Ruud/ Rheem
 - d. Bradford/White

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Water heaters shall each have a temperature-pressure relief valve sized to match heat input and set to relieve at 120 psi.
- B. Install temperature-pressure relief valve rated at MBH input of heater minimum on hot water heater and pipe discharge to directly above funnel of floor drain.
- C. Thermal Expansion Absorbers.
 - 1. Bladder type for use with potable water systems.
 - 2. Acceptable Products:
 - a. Therm-X Trol ST-5 by Amtrol
 - b. Equal as approved by Architect before bidding.

3.2 WATER TEMPERATURE

- A. Contractor shall be responsible to verify and/or change temperature settings on water heaters supplied on this project to meet requirements of Life Safety and Health Department Codes. Any setting above 120 deg. F. shall require warning labels placed on outside of water heaters in conspicuous places indicating water temperature setting and fact that any temperature above 120 deg. F. may be a hazard.

END OF SECTION 22 3330

SECTION 22 4001 – PLUMBING FIXTURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 22 05 01 apply to this Section.

1.2 SUMMARY

- A. Furnish and install plumbing fixtures as described in Contract Documents.
- B. Before fixtures are ordered, the Contractor shall submit a complete list of plumbing fixtures, giving the catalog number, cut and make, for approval. Fixtures shall not be ordered until this list is approved.

PART 2 - PRODUCTS

2.1 GENERAL

- A. Interior exposed pipe, valves, and fixture trim shall be chrome plated.
- B. Furnish and install the necessary plumbing fixtures in quantity as shown on plans. Provide all necessary valves, chrome plated 17 gauge or cast "P" traps, stops with risers, fittings, and accessories to make the job complete with the fixtures specified on the drawings. Exposed stops to be equal to Brasscraft with compression inlet, chrome plated nipples, cross handles, ¼ turn ball valves and flexible risers.
- C. Fixtures shall be PROFLO, Kohler, Crane, Briggs, Eljer, American Standard, or an approved equal. Specialties shall be Zurn, Josam, MiFab, J. R. Smith, Wade, or Watts.
- D. Toilet seat manufacturers shall be Beneke, Church, Olsonite, or Bemis.
- E. Carrier and wall hydrant manufacturers shall be Smith, Zurn, Wade, Josam, or Watts.
- F. Stainless steel sink manufacturers shall be Elkay or Just.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install fixtures including traps and accessories with accessible stop or control valve in each hot and cold water branch supply line.
- B. Mounting – Refer to Architectural Elevations.
- C. Make fixture floor connections with approved brand of cast iron floor flange, soldered or calked securely to waste pipe.
- D. Make joints between fixtures and floor flanges tight with approved fixture setting compound or gaskets.

- E. Caulk between fixtures and wall and floor with white butyl rubber non-absorbent caulking compound. Point edges.
- F. Cleanouts: Provide and set full size cleanouts at foot of each riser, and ends of branches from toilets, at points where a change of direction occurs, on exposed and accessible traps, at points where required to remove rust accumulation or other obstructions and as shown on plans. Set screw cap in cleanout with graphite paste. Location of all cleanouts subject to approval of inspector.
- G. Traps: Install "P" traps in branch lines from floor drains or where required. Traps installed in connection with threaded pipe shall be recess drainage pattern. Traps installed in connection with cast iron pipe shall be of the same quality and grade as the pipe. Traps installed in connection with fixtures shall have a seal of not less than 2" nor more than 4". Exposed traps shall be chrome plated cast brass or chrome plated 17 gauge tubular type. Provide trap primers as required by Code.

3.2 FIXTURE INSTALLATION

- A. Provide stop valves and 18" minimum air chambers on all water connections to fixtures. Furnish and install wall carriers for wall mounted fixtures, wood backing, where necessary, to be installed by General Contractor at the direction of this Contractor. Provide exact locations, including proper mounting heights, obtained from details on drawings and from manufacturer's specifications. Provide hudee rims for countertop installations.
- B. Interior exposed pipe, valves, and fixtures trim shall be chrome plated.
- C. Complete installation of each fixture including trap and accessories with accessible stop or control valve in each hot and cold water branch supply line. Make fixture floor connections with approved brand of cast iron floor flange, soldered or caulked securely to waste pipe. Make joint between fixture and floor flange tight with approved fixture setting compound or gaskets.
- D. Polish chrome finish at completion of project.
- E. Caulk between fixtures and wall and floor with white butyl rubber non-absorbent caulking compound. Paint all edges.
- F. Install fixtures and fittings as per local codes and manufacturer's instructions.

END OF SECTION 22 4001

END OF DIVISION 22